FINISHES SCHEDULE

ACT#1 **Corridor Ceiling Tile**
CGC Fineline DXF ceiling grid system, 4' cross tees, flat white, grid edge: FLB, wall molding detail: MS174, CGC Mars Climaplus ceiling tile, 2'x4' x 3/4" size, white
Supplier: CGC

BASE #1 **100mm Tile Base**

BASE #2 **100mm MDF Applied Base**

BASE #3 **100mm MDF Flush Base**

BASE #4 **75mm Tile Base**

BASE #5 **100mm Tile base w/ Tile Trim #1**

BASE #6 **100mm Metal Base**

BASE #7 **50mm Recessed Base for Tile #11**

BASE #8 **50mm Cove Base**
(for Quebec Series unglazed mosaic to match adjacent floor tile)

CARPET#1 ***(Prop Management Office)***
Carpet Tile, Stack 9 #04332, Colour: Luminous #75001, 24"x24" Unidirectional Installation, 100% Solution Dyed
Supplier: Tandus Flooring
Contact: Thomas Jackson
416-768-8939

CARPET#2 ***(Theatre)***
Broadloom Carpet, Data Stream #40036, Colour: Black Metallic #01962, 12' 6" (381 cm) wide, Dynex nylon, solution dyed..
Supplier: Tandus Flooring

CARPET#3 ***(Corridors, Typical)***
Broadloom Carpet, Trace #44053, Colour: Lead Mark #01910, 100% Solution Dyed
Supplier: Tandus Flooring

CARPET#4 ***(Corridors, Typical Accent)***
Broadloom Carpet, Alpaca 51050, Colour: Ostrich 00809, 100% Solution Dyed
Supplier: Tandus Flooring

GLASS#1 ***(TBD)***
1/4" or thickness as required, NG Grey Glass, star-fire, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: NGI Designer Glass
Contact: 905-738-1101

GLASS#2 ***(Lobby, Wall Paneling)***
1/4" or thickness as required, NGO Milk 200, star-fire, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: NGI Designer Glass

GLASS#3 ***(Dining Room/Party Room)***
1/4" or thickness as required, NGM/B Bronze Silk, star-fire, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: NGI Designer Glass

GLASS#4 ***(Lobby Fireplace Wall)***
Same as Mirror #1
Supplier: SPS Glass and Metals

GLASS#5 ***(---)***
1/2" or thk as required frosted glass.
Supplier: SPS Glass and Metals

HARDWOOD#1 ***(Party Room)***
Kentwood Originals, 7.5" wide, engineered plank floor
Col: Oak Silver Creek
Random plank installation, direct glue down.
Supplier: Metropolitan Hardwood Floors
Contact: Joe Cosentino
416-389-5003

HARDWOOD#2 **N/A**

MELAMINE #1 ***(Amenity Kitchen)***
Living Art, European Wood Surface #LW-3078 or approved alternative. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: By Kitchen Manufacturer/Living Art
Contact: Vladik Gladilen
647-893-2767

METAL #1 ***(TBD)***
Blackened Steel, gauge to be confirmed by fabricator, Refer to elevations for location.
Supplier: By Millworker/Option 3 Display
Contact: Tony Rizzo
514-333-9322

METAL #2 ***(Party Room, Divider Screen)***
Steel coil mesh, antique bronze finish, 1/8-20 gauge. Refer to elevations for location.
Supplier: By Millworker/Cascade Coil Drapery
Contact: 800-999-2645

METAL #3 ***(Party/Dining Room Accent/Party Room Bar)***
Brass to match Chemetal #325 Statuary Brass, gau ge to be confirmed by fabricator. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Lacquered, scratch resistant finish.
Supplier: By Millworker/McFaddens
Contact: Lucia Niu

METAL #4 ***(Fitness Room - Glazing Shoe)***
Satin Chrome from standard offering.
Supplier: Glazing Supplier

METAL #5 ***(Throughout)***
Stainless Steel
Supplier: Millwork

METAL #6 ***(Throughout)***
Black Hairline Stainless Steel
Supplier: Millwork

MIRROR#1 ***(Lobby, Fireplace Wall Accent)***
1/4" or thickness as required, NGM Black Mirror, star-fire, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: NGI Designer Glass

MIRROR#2 ***(Fitness)***
1/4" or thickness as required, clear mirror, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: NGI Designer Glass

PEDIMAT#1 ***(All Vestibules)***
Construction Specialties Gridline G6. Install according to LEED requirements, as shown on floor finishes plan, Install flush to adjacent floor finishes.
Supplier: Construction Specialties

PAINT#1 ***(General Walls, Throughout)***
Dulux, Song Porcelain #00NN 83/000, latex flat washable finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #2 ***(Ceiling, Throughout)***
Dulux, Song Porcelain #00NN 83/000, latex, flat finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #3 ***(P Mgmt Office Wall and Base)***
Dulux, Designer Grey, 50YY 63/041, latex, semi gloss for base and eggshell finish for walls. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #4 ***(Parking Level Elevator Doors and Frames)***
Dulux, Forest Black #30YY 10/038, latex, semi gloss finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #5 ***(Party Room Base)***
Dulux, Song Porcelain #00NN 83/000, latex, semi gloss finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #6 ***(Theatre Base)***
Dulux, Obsidian Glass, #00NN 13/ 000, latex, semi gloss finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #7 ***(Dining Room - Wall and Base)***
Dulux, Mansard Stone, #30YY 20/ 029, latex, flat washable finish for walls and semi gloss finish for base. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #8 ***(Changeroom Water Closet Walls)***
Dulux, Zeppelin, #30YY 46/ 036, latex, flat washable finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #9 ***(Lobby General)***
Refer to Paint #1.

PAINT #10 ***(Suite Entry/typ doors and Frames)***
Dulux, Forest Black #30YY 10/038, latex, flat finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #11 ***(Typ Corridors Base)***
Dulux, Forest Black #30YY 10/038, flat finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

PAINT #12 ***(Fitness Room Base)***
Refer to Paint #7.

PAINT #13 ***(Changeroom Water Closet Walls)***
Refer to Paint #8.

PAINT #14 ***(Typ Corridor Utility doors - Electrical Closet, Garbage Chute, Exit Stairs)***
Dulux, Stratosphere, #40YY 73/ 028, latex, semi gloss finish. Refer to elevations and wall finishes plan for location.
Supplier: Dulux

P.LAM#1 ***(Prop Management Kitchen/Admin)***
Arborite, Snow White, #S-417 CA, Refer to elevations for location.
Supplier: Wilsonart
Contact: Janet Bascoe-Spencer
905.565.1255 x5731

P.LAM#2 ***(Prop Management Kitchen/Admin)***
Arborite, Fumed American Elm, #W-468 EV, Refer to elevations for location.
Supplier: Wilsonart

P.LAM#3 ***(Concierge Millwork / Parcel Storage)***
Arborite, TBD, Refer to elevations for location.
Supplier: Wilsonart

RUBBER #1 ***(Gym Floor)***
Johnsonite Triumph, 610mm x 610mm x 9.5mm, Colour: #29 Moon Rock, square edge tiles, hammered surface texture (SMH). Install as per manufacturer's directions. Refer to floor finish plan for location.
Supplier: Johnsonite
Contact: Tom Joyce
905.886.8081

SP. MATERIAL #1 ***(Lobby Column Covers)***
Fused Metal Column Covers
Col: Fused Graphite, Finish: Sandstone
2.5" high Top trim and Bottom Trim, Vertical joint with no reveals
Covers come standard 120"h - stack with hairline seam to achieve heights lin lobby. Install as per manufacturer's directions. Refer to wall finish plan for location.
Supplier: Forms and Surfaces
Contact: Jennifer Heimpel
800.451.0410

SLAB#1 ***(Millwork, Concierge Desk)***
Cipollino, polished.
Supplier: Clot
Contact: Aaron Huynh
416.739.8000 x8888

SLAB#2 ***(Millwork, Concierge Desk)***
Nero Voda, cross cut, honed.
Supplier: Clot

SLAB#3 ***(Lobby, Elevator surround)***
N/A
Supplier: Clot

SLAB#4 ***(Amenity Kitchen Counter, Party Room Bar Table)***
3/4" Slab, Caesarstone #5110 Alpine Mist, edges to be polished.
Supplier: Caesarstone
Contact: Michelle Greco
416-476-6949

SLAB#5 ***(Prop Management Kitchen/Admin)***
3/4" Slab, Caesarstone #2141 Blizzard, edges to be polished.
Supplier: Caesarstone

SLAB#6 ***(Changeroom)***
3/4" Slab, Caesarstone #4003 Sleek Concrete, edges to be polished.
Supplier: Caesarstone

SLAB#7 ***(Party Room & Theatre Kitchen Counter)***
3/4" Slab, Paragon Black, polished, edges to be polished.
Supplier: Clot

SLAB#8 ***(Party Room Bar Counter)***
3/4" Slab, same as slab #7
Supplier: Clot

TILE #1 ***(Lobby Flooring)***
60x120cm porcelain tile, Stone Project, Grey Fakta Naturale, 60x120, grout colour TBD. Refer to floor finish plan for location.
Supplier: Stone Tile
Contact: Debra Rubin
416-515-9000 x245

TILE #2A ***(Lobby Flooring Accent)***
20x120cm porcelain tile, Stone Project, Grey Fakta Naturale, grout colour TBD
Refer to floor finish plan for location.
Supplier: Stone Tile

TILE #2B ***(Lobby Flooring Accent)***
20x120cm porcelain tile, Stone Project, Grey Fakta Lappato, grout colour TBD
Refer to floor finish plan for location.
Supplier: Stone Tile

TILE #3 ***(Changerooms Flooring)***
15x90cm porcelain tile - ***cut down to 15x15cm square format***, StoneBox, Colour: Bright Grey, natural finish, grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location.
Supplier: Stone Tile
Contact: Debra Rubin
416.515.9000 x299

TILE #3a ***(Washroom Walls)***
Same as tile #3, size: 150mmx300mm
Supplier: Stone Tile
Contact: Debra Rubin
416.515.9000 x299

TILE #4 ***(Changeroom Walls)***
4x16" ceramic tile, Colour & Dimensions Collection, Arctic White Bright, #QT.CD.ARW.0416.BR, grout TBD. Install as per manufacturer's directions. Refer to wall finishes plan for location. Ensure grout lines align as per wall finishes plan.
Supplier: Olympia Tile
Contact: Lucy Capoblanco
416-785-9555 x254

TILE #5 ***(Staff W/C Shower Changeroom Walls)***
Same as Tile #4

TILE #6 ***(Kitchen Flooring)***
12x24" porcelain tile, Metal Gloss, Steel Wool, #MAR0349MGFL02, grout TBD. Install as per manufacturer's directions. Refer to floor finish plan for location.
Supplier: Division 9
Contact: Mary Kouros
905.789.3756 x2544

TILE #7 **N/A**

TILE #8 ***(Mail Room Flooring)***
60x120cm porcelain tile, Stone Project, Grey Fakta Naturale, 60x120, grout colour TBD. Refer to floor finish plan for location.
Supplier: Stone Tile

TILE #9 ***(Prop Management Kitchen/Admin)***
Porcelain tile, Versus, Ice Natural #VEIC1224, 12"x24", grout colour TBD.
Install as per manufacturer's directions. Refer to floor finish plan for location.
Supplier: Centura

TILE #10 ***(Whirlpool Room Flooring)***
Refer to Tile #3
Supplier: Stone Tile

TILE #11 ***(Lobby Recessed Base)***
Unilotor Super Black Polished BY,UN,BLK,1224, cut to size per detail. Install as per manufacturer's directions. Refer to floor finish plan for location.
Supplier: Olympia Tile

TILE #12 ***(Changerooms, Showers)***
Mosaic tile, Quebec, Dark Grey FS, 2"x2", unglazed, #OD.QC.STR.0202.FS
Refer to floor finish plan for location.
Supplier: Olympia Tile

TILE #13 ***(P Level Elevator Lobby Walls)***
12x24" porcelain tile, Montecassino Matte, vein cut, Grey, natural finish, #ZS.MC.GRY.1224.MT.VC, grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location.
Supplier: Olympia Tile

TILE #14 ***(P Level Elevator Lobby Flooring)***
12x24" porcelain tile, Evolve Night Black #WA.EV.NHT.1224, grout colour TBD. Install as per manufacturer's directions. Refer to floor finishes plan for location.
Supplier: Olympia Tile

TILE #15 ***(Staff WC Changeroom Floor)***
12x24" porcelain tile, Evolve, Color: Night (Black), natural finish, #WA.EV.NHT.1224, grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location.
Supplier: Olympia Tile

TILE #15a ***(Staff WC Changeroom Cove Base)***
Quebec Series unglazed mosaic 2x2 cove base, to match Tile #15 (colour TBD)
Supplier: Olympia Tile

TILE #16 ***(Whirlpool Room Walls)***
15x90cm porcelain tile, StoneBox, Colour: Bright Grey, natural finish, grout colour TBD. Install as per manufacturer's directions. Refer to elevations for location.
Supplier: Stone Tile

TILE #17 ***(Elevator Lobby Wall Ground Floor)***
Changed to Glass #2
Supplier: Stone Tile

TILE #18 ***(Typ Corridor Walls @ Elevator)***
15x90cm porcelain tile, StoneBox, Colour:, polished finish, grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location.
Supplier: Stone Tile

TILE #19 ***(Public Barrier Free Washroom Walls)***
3"x10" ceramic tile, Liverpool, col: Portland, glossy grout TBD. Install as per manufacturer's directions. Refer to floor/wall finishes plan for location. Ensure grout lines align as per floor finishes plan/elevations..
Supplier: Cera Gres
Contact: Jessica Cano
416-286-3553

TILE #20 ***(Changerooms - Cove Base)***
Quebec Series unglazed mosaic 2x2 cove base, to match Tile #3 (colour TBD)
Supplier: Olympia Tile

TILE #21 **(Barrier Free Washroom Mural)**
Bisazza mosaic mural, 10mm x 10mm, Sfumature shading blend, colour: Gelsomino. Install as per manufacturer's directions, Refer to wall finishes plan for location. Ensure grout lines align as per floor finishes plan/elevations..
Supplier: Stone Tile Stone Tile

TILE #22 **(Garbage Room Floor)**
50mm x 50mm unglazed Quebec Mosaics, Col: TBD. Install as per manufacturer's directions. Refer to floor/wall finishes plan for location. Ensure grout lines align as per floor finishes plan/elevations..
Supplier: Olympia

TILE #23 **(Garbage Room Walls)**
300mm x 600mm porcelain tile, Elger Antracite, grout TBD. Install as per manufacturer's directions. Refer to floor/wall finishes plan for location. Ensure grout lines align as per floor finishes plan/elevations..
Supplier: Clot

TILE# 24 ***(Ground Flr Interior Whirlpool)***
1" x 1" unglazed porcelain tile, Quebec Series, col: black
Refer to floor finish plan for location.
Supplier: Olympia Tile
Contact: Lucy Capoblanco
(416)785-9555

TILE# 25 ***(Ground Flr Interior Whirlpool Nosing)***
1" x 1" unglazed porcelain tile, Quebec Series, col: arctic white
Refer to floor finish plan for location.
Supplier: Olympia Tile

TILE# 26 ***(Ground Flr Fitness Wall Tile)***
2"x 8" glazed cermaic tile, Colour and Dimension Series, col: arctic white
Refer to floor finish plan for location.
Supplier: Olympia Tile

TILE TRIM #1 **(Exposed Wall Tile Edges)**
Schluter Jolly, Brushed Nickel, size to suit tile.

TILE TRIM #2 **(Laminate to Laminate)**
Schluter Schiene, Brushed Nickel, size to suit laminate floor.

WALLCOVERING #1 ***(Corridors)***
Vinyl Wallcovering, Custom Type II wallcovering based on Vescom 05 - Tempe #766.12. Refer to wall finishes plan and elevations for location.
Supplier: Metro Wallcovering
Contact: Charley Binder
905.738.7461

WALLCOVERING #2 ***(P Level Elevator Lobby)***
Vinyl Wallcovering, Custom Type II wallcovering based on Vescom 05 - Albert #778.09, Refer to wall finishes plan and elevations for location.
Supplier: Metro Wallcovering

WALLCOVERING #3 ***(Party Room)***
Vinyl Wallcovering, Embassy EM1-4549, 54" wide, Type II, Class A. Refer to wall finishes plan and elevations for location.
Supplier: Metro Wallcoverlng

WALLCOVERING #4 ***(Dining Room Accent)***
Custom Vinyl Mural Wallcovering, image/graphic to be selected by designer and printed on vinyl substrate, Type III, Class A. Refer to wall finishes plan and elevations for location.
Supplier: Metro Wallcoverlng

WALLCOVERING #5 ***(Amenity Dining Room & Kitchen)***
Vinyl Wallcovering, Koroseal, Montage, Café Noir 8721-85, 54" wide, Type II, Class A. Refer to wall finishes plan and elevations for location.
Supplier: Metro Wallcoverlng

WALLCOVERING #6 ***(Theatre)***
Vinyl Wallcovering, Colour and Design, Obana Glint, CD2-OBG-45, Black Mica, 54" wide, Type II, Class A. Refer to wall finishes plan and elevations for location.
Supplier: Metro Wallcoverlng

WALLCOVERING #7 ***(Gr Floor Public Spaces)***
Refer to Wallcovering #3.

WALLCOVERING #8 ***(Gr Floor Fitness)***
Vinyl Wallcovering, Koroseal, Patana, Cotton, 0721-03, 54" wide, Type II, Class A. Refer to wall finishes plan and elevations for location.
Supplier: Metro Wallcoverlng

WALLCOVERING #9 ***(Gr Public Washroom)***
Vinyl Wallcovering, Colour and Design, Canton Rainsilk, CD2-CTR-13, Clean Slate, 54" wide, Type II, Class A. Refer to wall finishes plan and elevations for location.
Supplier: Metro Wallcovering

WOOD#1 ***(Party Room Millwork - Throughout)***
TAY (KOTO) 04.005 veneer, clear coat 10% sheen of high quality urethane to be applied for protection, solids as required. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: By Millworker/Materials Inc.
Contact: Leonardo Flaschi
201.968.0101

WOOD#2 ***(Lobby Millwork Throughout - Fin Detail)***
Walnut, flat cut, MI-C3216, veneer, oiled finish. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: By Millworker/Materials Inc.

WOOD#3 ***(Typ Suite Door Surrounds)***
Walnut, flat cut, MI-C3216, veneer, oiled finish. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: By Millworker/Materials Inc.

WOOD#4 ***(Lobby Millwork - Ceiling)***
Koroseal Arbor Series Wood wallcovering, Walnut, flat cut, veneer applied directly onto drywall ceiling. Flame Spread rating: 10, Class A fire rating. Supplier to create install pattern. Book matched as required. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location.
Supplier: Metro Wallcovering
Contact: Charley Binder

FABRICS

FAB#1 ***(TBD)***
Black cowhide leather, Royal Hide - Black RH53
Supplier: Edelman
Contact: Benett Mills
1.800.866.8339

FAB#2 ***(TBD)***
White cowhide leather, Dream Cow - Fresh Snow DRC24
Supplier: Edelman

FAB#3 ***(TBD)***
Black cowhide leather, All Grain - Black AG05
Supplier: Edelman

FAB#4 ***(TBD)***
Light grey chenille, Venice 061, 54"W
Supplier: Avant Garde
Contact: Krista Skov
905.669.9474 x24

FAB#5 ***(TBD)***
Mottled grey fabric, KT Collection, Hourglass K1523/24, Colour: Misty, 56" W
Supplier: Knoll Textiles
Contact: Kim Huynh
416.682.2107

FAB#6 ***(TBD)***
Black fabric, Venetian, Colour: Charcoal, #611-016, 54"W
Supplier: Mayer Fabrics/Hollyhock Design Options
Contact: Fay Paterson
416.525.7147

FAB#7 ***(Drapery)***
Charcoal fabric, Ultrasoft - 21, Colour: Charcoal, 45" W
Supplier: Kravet
Contact: Brenda Bradley
905.607.0706 x811

FAB#8 ***(Theatre Acoustic Panels)***
Charcoal fabric, Liam, Colour: #9BS6601, 55" W.
Supplier: Joanne Fabrics
Contact: 905.491.3900

PLUMBING SCHEDULE

P1 - TOILET ***(Ground Flr W/C / 2nd floor change room, 6th floor changeroom, Ground Floor Fitness)***
Kohler HighCliff toilet bowl K-4368, white finish, c/w Lustra open front seat K-4368; col: White. Exposed toilet flushometer, 1.28 gpf, K-13516, polished chrome finish. Refer to Furniture & Power plan for locations.
Supplier: Kohler
Contact: Arnel Go
416-716-0536

P2 - BASIN ***(Ground Floor W/C/P1 WC)***
American Standard Wheelchair Users Lavatory. Vitreous china, 9140,047 Center Hole Only, 20"x27" Colour: White
Supplier: American Standard
Contact:

P3 - FAUCET ***(Ground Floor W/C)***
Hansgrohe Metris S Single Hole Faucet c/w pop up, 31060001, Chrome Finish. Install according to OBC requirements for Barrier Free.
Supplier: Amati Plumbing

P4 - SINK ***(Ground Floor Changerooms)***
White vitreous china under counter sink # PS-105 , 16" x16" x 6-3/4"h, c/w recommended drain. Refer to Furniture & Power plan for locations.
Supplier: Cantrio Koncepts

P5 - SHOWER HEAD ***(Ground Floor Changerooms)***
Hansgrohe, Raindance Connect Shower System, wall mounted shower head and hand shower, model #27164001, chrome finish. Complete with required rough-ins, wall outlets and temp control trims.
Supplied By: Amati

P6 - FAUCET ***(Ground floor Changerooms)***
Hansgrohe Metris S Faucet # 31163001 with Preset Temperature control. Battery operated (finished). Chrome Finish.
Supplier: Amati

P7 - SINK ***(Ground Floor Amenity Bar)***
Stainless steel undermount sink KSS-003, c/w mtg hardware and all parts. Refer to Furniture & Power plan for locations.
Supplier: Cantrio Koncepts

P8 - SINK ***(Ground Floor Amenity Kitchen)***
Stainless steel undermount sink KSS-005, 18"x23"x10.5" c/w mtg hardware and all parts. Refer to Furniture & Power plan for locations.
Supplier: Cantrio Koncepts

P9 - FAUCET ***(Ground Floor Amenity Kitchen)***
Blanco Culina Mini Pull Down Kitchen Faucet, 441624, pull out single spray, swivel spout, chrome finish, 1.8gpm. Refer to Furniture & Power plan for locations.

P10 - FAUCET ***(Ground Floor Bar)***
Blanco Culina Mini Pull Down Kitchen Faucet, 441624, pull out single spray, swivel spout, chrome finish, 1.8gpm. Refer to Furniture & Power plan for locations.

P11 - LINEAR FLOOR DRAIN ***(Amenity Showers)***
Infinity drain, d=AS 65 , complete kit, site sizable, Size per plan. Polished Stainless finish. Complete with all necessary components. Refer to Furniture and Power plan for locations. Consult with landscape architect.
Supplier: Infinity Drain

P12 - SINK ***(Property Management Office Kitchenette, P1 Level Kitchenette)***
Stainless steel undermount sink KSS-2018, 20"x18"x6" c/w sound dampening pads, hardware and all parts. Refer to Furniture & Power plan for locations
Supplier: Cantrio Concepts

P13 - FAUCET ***(Property Management Office Kitchenette, P1 Level Kitchenette)***
American Standard Collina Single Control kitchen faucet, pull down spray, chrome finish, 4717 300, 1.8gpm, Refer to Furniture & Power plan for locations.

P14 - BOTTLE FILLING STN ***(Fitness Area Ground Floor)***
Elkay EZH20 Bottle filling station with Bi-Level EZ Cooler Model LZSTL8WS . Refer to Furniture & Power plan for locations.
Supplier: Elkay

P15 - SHOWER HEAD **(P1 Level Changeroom)**
American Standard, Serin Shower System Kit, model # 2064.724, 3 function adjustable hand shower, hose, wall supply, and slide bar, chrome finish. Complete with required rough-ins, control valves, trim kit and accessories.
Supplied By: American Standard
Contact: Fedele Rossi
(647)201-6633

P16 - BASIN **(P1 Level Changeroom)**
Same as P2

P17 - FAUCET **(P1 Level Changeroom)**
American Standard Serin Single hole faucet, chrome finish, 2064 101, with pop up drain, 1.8gpm. Refer to Furniture & Power plan for locations.

P18 - BARRIER ADJ SHOWER KIT **(Ground floor/P1 barrier free washroom)**
Cabana 75101 Build a Shower Stiki Shower rail kit. Incl Bar, hose and hand shower, Chrome. Mounting height according to OBC Barrier free requirements.

P19 - FOOT SHOWER ***(9th Floor Pool (outdoors))***
Foot shower at deck floor level c/w ADA metered push valve 32" free-standing foot shower, FSFS-200-ADA, polished chrome finish. Refer to Furniture and Power plan for locations. Consult with landscape architect.
Supplier:

EQUIPMENT SCHEDULE

E1 - INTEGRAL SOAP DISPENSER ***(washrooms)***
Stern Engineering Commercial Electronic smart touch free soap dispenser. Ref # 235900
Supplier: Stern Engineering

E2 - TOWEL DISPENSER ***(washrooms)***
Bobrick surface mount dispenser/disposal fixture B-43699, stainless steel satin finish
Supplier: Citywide door and hardware

E3 - TOILET TISSUE DISPENSER ***(washrooms)***
Bobrick surface mount multi roll toilet tissue dispenser, model B-2888 stainless steel satin finish
Supplier: Citywide door and hardware

E4 - FEMININE NAPKIN DISPOSAL ***(washrooms)***
Bobrick surface mount feminine napkin disposal modelB-254 stasinless steel satin finish
Supplier: citywide door and hardware

E5 - GRAB BARS ***(washrooms)***
Bobrick grab bar system B-6206 series, complete with concealed mounting, contractor to ensure system complies with OBC, stainless steel finish
Supplier: citywide door and hardware

E6 - HOOK ***(washrooms)***
Bobrick surface mounted robe hook modelB-6717 stainless steel satin finish, refer to plans for location
Supplier: Citywide door and hardware

E7 - MAILBOXES ***(Mailroom)***
Riopel, model 4500-D192, rear loading horizontal mailboxes, refer to elevation for location
Supplier: Riopel
Contact: Order desk
1-514-034-0385

E8 - FRIDGE ***(Party room Kitchen)***
24" integrated refrigerator, per building standard. Panel colour TBD.
Supplier: Appliance Canada
Contact: John Outahen
905-660-2424

E9 - DISHWASHER ***(Party room Kitchen)***
24" fully integrated dishwasher, per building standard. Panel colour TBD.
Supplier: Appliance Canada

E10 - MICROWAVE ***(Party room kitchen)***
24" built in stainless steel microwave AEG MCD2665EM, complete with trim kit
Supplier: Appliance Canada

E11 - ENTERPHONE ***(entry)***
By client

E12 - LOCKERS ***n/a***

E13 - WATER FOUNTAIN ***(Exercise Room)***
Refer to P14 for spec.

E14 - TV ***(Billiards Room)***
46",By client

E15 - TV ***(Dining Room)***
46" By client

E16 - TV ***(Bar)***
46" TV mounted behind mirrored wall panelling. TBD

E17 - TV **(Party Room)**
65", by client

E18 - B.F. Mirror ***(b.f. washroom, P1 Level, 9th Floor)***
Bobrick B293 1836, fixed position tilt mirror
Supplier: Citywide door and hardware

E19 - TBD

E20 - Photocopier ***(Management Office)***
By client

E24 - Warming Drawer ***(Kitchen)***
Porter and Charles WD60-14 24" stainless steel warming drawer, 5.5" high
Supplier: Appliance Canada

E25 - Warming Drawer ***(Kitchen)***
Porter and Charles WD60-21 24" stainless steel warming drawer, 8.2" high
Supplier: Appliance Canada

E26 - Elec Fireplace ***(Dining Room)***
Napoleon Slimline EFL48H Slimline Series fireplace, 23x48x3-3/4", recessed.
Supplier: Odyssey Fireplaces

E27 - Whirlpool ***(Changerooms)***
Custom Concrete Whirlpool, with jets, as per pool supplier specifications.
Supplier: Advanced Commercial Pool and Spa

E28 - WALL MNT SOAP DISPENSER ***(P1 and 9th Floor Washrooms)***
Bobrick Contura series recessed soap dispenser, model #B-4063, chrome finish
Supplier: Citywide Door & Hardware

E29 - UNDER COUNTER FRIDGE ***(Prop Management/Bar Area)***
Panel ready - 24" under counter fridge, Marvel ML24BRF3LP, handing as per elevation.
Supplier: Appliance Canada

E30 - ELEC FIREPLACE ***(Dining Room)***
Custom Electric fireplace per elevation. Provide shop drawings for approval.
Supplier: Odyssey Fireplaces

E30 - ELEC FIREPLACE ***(Lobby)***
Custom Electric fireplace per elevation, approx. 10' L. Provide shop drawings for approval.
Supplier: Odyssey Fireplaces

DO NOT SCALE DRAWINGS.

CONTRACTOR MUST VERIFY ALL DRAWINGS, DIMENSIONS, DETAILS AND SPECIFICATIONS, AND REPORT ANY DISCREPANCIES TO *UNION 31 INC.* BEFORE PROCEEDING WITH WORK. MATERIALS MAY NOT BE SUBSTITUTED WITHOUT WRITTEN APPROVAL FROM *UNION 31 INC.*

ALL DRAWINGS AND SPECIFICATIONS ARE INSTRUMENTS OF SERVICE AND THE PROPERTY OF *UNION 31 INC.* WHICH MUST BE RETURNED AT THE COMPLETION OF THE WORK.

PRINTED: 22-Jan-16

NO.	DATE	COMMENTS	INI
17	22 JAN / 16	ISSUED FOR SITE INSTRUCTION #3	CB
16	21 JAN / 16	ISSUED FOR PAINT / WALLPAPER TENDER	CB
15	22 SEPT/ 15	ISSUED FOR DRYWALL TENDER ADNDM #1	CB
14	8 SEPT / 15	ISSUED FOR TRIM CARPENTRY	
		ADDNDM#2 / SITE INSTRUCTION #2	CB
13	24 AUG / 15	RE- ISSUED FOR DRYWALL TENDER	CB
12	21 AUG / 15	ISSUED FOR TRIM CARPENTRY ADNDM#1	CB
11	20 AUG / 15	ISSUED FOR DRYWALL TENDER	CB
10	15 JULY / 15	ISSUED FOR TRIM CARPENTRY TENDER	CB
09	16 JUNE / 15	ISSUED FOR FINISH CARPENTRY	CB
08	11 JUNE / 15	SITE INSTRUCTION #1	CB
06	26 MAY / 15	HARDWOOD AND LAMINATE CLARIFICATION - ADDENDUM #1	CB
05	13 MAY / 15	ADDENDUM #2	CB
03	06 MAR / 15	ISSUED FOR TILE TENDER	AP
02	26 JAN / 15	ISSUED FOR TENDER	AP
01	22 AUG / 14	ISSUED FOR PERMIT	AP

REVISIONS:

UNION31

UNION31 INC.
183 BATHURST STREET, STE 201
TORONTO, ON, M5T 2R7, CANADA
TEL: 416-597-1576 FAX: 416-597-2139

PROJECT NAME:
ALEXANDRA PARK
MAIN BUILDING
BLOCK 11
ON, Canada

PROJECT NO.: 13-949

DRAWING/S:
FINISHES SCHEDULE
PLUMBING & EQUIPMENT SCHEDULE

DATE STARTED: 07 AUG / 13
SCALE: NTS
DRAWN BY: AP
APPROVED BY: KC
DRAWING NO.: ID 0.0.1