

PIPE SHAFT A: 14/F | NTS



PIPE SHAFT B: 14/F | NTS



PIPE SHAFT C: 14/F | NTS



NOTE:
- ALL DIMENSIONS IN MM.
- HEIGHT OF FCU IS 2,023.

INSUITE FCU DIMENSIONS | NTS

UNIT	NAME	AREA (SQ. FT.)	# OF WR	# OF POWDER	SIZE (T)	FIXTURE UNITS	BR	SQ. FT/T
PH05	3C	990	2	Ø	2	16	3	495
PH11	1C+D1	590	2	Ø	1	16	1	590
PH12	1C+D1	590	2	Ø	1	16	1	590
PH19	2L	755	2	Ø	1.5	16	2	503
PH20	2H	740	2	Ø	1.5	16	2	493
PH21	2LR2	755	2	Ø	1.5	16	2	503
PH29	1A+M3	580	1	Ø	1	10	1	580

GRILLE SIZING TABLE		
DESIGNATION	SIZE	L/S (UNLESS SPECIFIED ELSEWHERE)
SG-A	300x100	47-70
SG-B	300x150	71-93
SG-C	400x150	94-140
SG-D	450x150	141-188
EG-A	150x150	35
W-1	225x200	210mm(L)
W-2	425x200	INSULATED
W-3	625x200	WALL BOX

VERTICAL FAN COIL SIZE		
DESIGNATION	MODEL	W x D
FCU-1T	450	508x660
FCU-1.5T	600	508x660
FCU-2T	800	508x660
FCU-2.5T	1000	559x660
FCU-3T	1200	559x660

NOTE:
A MIN. OF 125mm IS REQUIRED ON THE SIDE OF PIPE RISER.

DUCT SIZING TABLE (4.0ø m/s, 800 FPM)					
DESIGNATION	L/s	DUCT SIZE	DESIGNATION	L/s	DUCT SIZE
A	47	100x150	G	189	350x150
B	71	150x150	H	236	450x150
C	94	200x150	J	283	500x150
D	118	200x150	K	330	600x150
E	141	250x150	L	377	500x200
F	165	300x150			

GENERAL NOTES:

1) CONTRACTOR SHALL CO-ORDINATE ARCHITECTURAL, STRUCTURAL, LIGHTING, HVAC, SPRINKLER DRAWINGS TO AVOID AREAS OF CONFLICT AND TO MAINTAIN CEILING HEIGHTS.

2) CONTRACTOR SHALL REPORT ALL DISCREPANCIES AND AREA OF CONFLICTS TO THE ENGINEER PRIOR TO WORK BEGINS.

3) PROVIDE EXPANSION CHAMBERS FOR ALL KITCHEN SINKS.

4) SEE INSTALLATION DETAILS DRAWING FOR WASHER DOM. H+C WATER, SANITARY CONNECTION DETAILS.

5) SUPPLY AND INSTALL COMPLETE DOMESTIC HOT AND COLD WATER LINES, SANITARY AND VENT LINES TO EACH FIXTURE /EQUIPMENT INCLUDING WATER CLOSETS, LAVATORIES, BATHS, SHOWERS, KITCHEN SINK, WASHING MACHINES, DISHWASHERS, AND FLOOR DRAINS. KITCHEN SINK, LAVATORIES, WATER CLOSETS AND WASHING MACHINE TO BE C/W LOCALIZED SHUT-OFF VALVES.

6) ALL VENT PIPE INSTALLATION TO COMPLY WITH PLUMBING CODES.

7) FOR D.H.+C. W. RISER SIZES, REFER TO RISER DIAGRAM

8) FIRE DAMPERS ARE REQUIRED TO BE LISTED AND ARE TO HAVE FIRE PROTECTION RATING OF THE PENETRATED FIRE SEPARATION.

9) THE PIPING PENETRATING THE VARIOUS FIRE SEPARATION IS REQUIRED TO BE FIRESTOPPED WITH A LISTED FIRESTOPPING MATERIAL IN ACCORDANCE WITH OBC ARTICLE 3.1.9.1

10) THE FIRE HOSE CABINET THAT ARE RECESSED INTO THE EXIT STAIR SHAFTS ARE REQUIRED TO BE SEPARATED FROM THE EXIT STAIR BY A 2 HR. FIRE SEPARATION.

11) NO FLEXIBLE DUCT SHALL BE USED FOR ANY IN-SUITE DUCTWORK.

12) PROVIDE 25MM EXTERNAL INSULATION TO ENTIRE FRESH AIR DUCT FROM EXTERIOR WALL TO ERV FAN COIL UNIT.

13) DRYER EXHAUST DUCT SHALL BE SMOOTH AND CORROSION-RESISTANT MATERIAL (FLEXIBLE CONNECTION IS NOT ACCEPTABLE).

ACOUSTIC NOTES:

1) ALL HORIZONTAL SUPPLY AIR DUCTWORK SHALL BE C/W 25MM INTERNAL ACOUSTIC LINING AND SHALL BE SUSPENDED ON RUBBER PADS IN THE HANGERS. ELBOWS SHALL BE COMPLETE WITH TURNING VANES..

2) ALL SYSTEM/DOMESTIC PIPE LOOPS OR OFFSETS WHICH ARE 50MM DIA. AND LARGER SHALL BE ISOLATED USING NEOPRENE-IN-SHEAR HANGERS, AND ADDITIONAL 25 MM THICK RIBBED OR WAFFLED NEOPRENE PADS IN THE SADDLES OF CLEVIS HANGERS.

3) ALL PIPES SMALLER THAN 50MM DIA. SHALL BE ISOLATED WITH 9MM THICK RIBBED OR WAFFLED RUBBER PADS IN HANGER SADDLES.

CLEAR FLOOR TO UNDERSLAB = 3270mm
CLEAR PRODUCT= 2700mm
COMPLETE DROP CEILING = 570mm

NOTES:

1. NORTH F/A SHAFT B FROM G/F TO 14/F DUCT SERVING CORRIDOR FROM G/F TO 14/F. SEE VENTILATION RISER DIAGRAM FOR DETAILS.
2. NORTH SHAFT B F/A SERVING FROM G/F TO 14/F. F/A DUCT SERVING CORRIDOR FROM G/F TO 14/F. SEE VENTILATION RISER DIAGRAM FOR DETAILS.
3. PIPE SHAFT - REFER TO PIPE DIAGRAM FOR DETAILS.
4. 150ø KITCHEN / DRYER / W/R / FCU INTAKE / FCU EXHAUST DUCT. (TYPICAL UNLESS OTHERWISE NOTED)
5. SEE DWG. M-33 FOR PIPING CONNECTION DETAIL.
6. 50ø SWR.
7. 32ø SWR.
8. 100ø SWR.
9. 150ø SWR.
10. 75ø SWR.
11. 600ø GARBAGE CHUTE.
12. 19ø DHWR.
13. 25ø DHWR.
14. 32ø DHWR.
15. 38ø DHWR.
16. 50ø DHWR.
17. 150ø CWS & R.
18. 250ø COMBUSTION AIR INTAKE AND 250ø EXHAUST UP THROUGH ROOF C/W TERMINATION FITTING, AS PER MANUFACTURER'S INSTALLATION MANUAL AND TSSA REQUIREMENTS.
19. 300ø COMBUSTION AIR INTAKE AND 225ø EXHAUST UP THROUGH ROOF C/W TERMINATION FITTING, AS PER MANUFACTURER'S INSTALLATION MANUAL AND TSSA REQUIREMENTS.
20. 100ø STM c/w.
21. 100ø RWL DOWN.
22. 100ø RWL FROM ABOVE.
23. 400x200 INTAKE LOUVRE c/w MOTORIZED DAMPER, FIRE DAMPER & WIRE MESH.
24. REFRIGERANT PIPES FROM SPLIT COOLING INDOOR UNIT (SAC-IT) TO CONDENSING UNIT (SCU-IT). PIPE SIZING AND INSTALLATION AS PER MANUFACTURER'S RECOMMENDATIONS (TYPICAL).

LEGEND
MECHANICAL

SYMBOL	DESCRIPTION
	SUPPLY AIR DIFFUSER
	SUPPLY AIR TROFFER
	LINEAR SUPPLY DIFFUSER
T	THERMOSTAT
S	FAN SWITCH
	RETURN AIR GRILLE
	EXHAUST AIR GRILLE
	SUPPLY DUCT UP
	SUPPLY DUCT DOWN
	RETURN DUCT UP
	RETURN DUCT DOWN
	EXHAUST DUCT UP
	EXHAUST DUCT DOWN
FD	FIRE DAMPER
BD	BALANCING DAMPER
MD	MOTORIZED DAMPER
MFD	MOTORIZED FIRE DAMPER
BDD	BACKDRAFT DAMPER
OBD	OPPOSED BLADE VOLUME CONTROL DAMPER C/G LOCKING QUADRANT
TV	TURNING VANES
FC	FLEXIBLE CONNECTION
AI	ACOUSTIC INSULATION
XX/ A	TYPE OF EQUIPMENT / EQUIPMENT IDENTIFICATION
XXX/ XXX	TYPE OF DIFFUSER OR GRILLE / GRILLE SIZE OR DIFFUSER NECK SIZE
XXX	AIRFLOW (CFM OR L/S)
S A	STARTER (S PHASE / PHASE)
S	IN-SUITE ERV MASTER SWITCH
S	FAN SWITCH / IN-SUITE ERV OVERRIDE BUTTON
CO	CO SENSOR
G	GAS LINE
G	GAS METER
G	GAS COCK
PRV	PRESSURE REDUCING VALVE
SAG	SANITARY ABOVE GRADE
SBG	SANITARY BELOW GRADE
SVAG	STORM ABOVE GRADE
SVBG	STORM BELOW GRADE
DCW	DOMESTIC COLD WATER
DHW	DOMESTIC HOT WATER
DHWR	DOMESTIC HOT WATER RECIRCULATION
V	SANITARY VENT
WM	WATER METER
FD	FLOOR DRAIN
FFD	FUNNEL FLOOR DRAIN
HD	HUB DRAIN
RD	ROOF DRAIN
SLD	SLAB DRAIN
AD	AREA DRAIN
BL-AD	BI-LEVEL AREA DRAIN
CB	CATCH BASIN
ST	SANITARY TRAP
	ELBOW UP
	ELBOW DOWN
CO	WALL CLEANOUT
CO	FLOOR CLEANOUT
HB	HOSE BIBB
NFHB	NON-FREEZE HOSE BIBB
GV	GLOBE VALVE
GV	GATE VALVE
BV	BALL VALVE
BV	BUTTERFLY VALVE
PRV	PRESSURE REDUCING VALVE
CV	CHECK VALVE
C	CAP
CA	COMPRESSED AIR OUTLET
BFV	BACKFLOW PREVENTER
CBV	CIRCUIT BALANCING VALVE
	MULTIPLE PIPES / - DENOTES NO. OF PIPES
T	TEMPERATURE SENSOR
T	THERMOMETER
2W	2-WAY MODULATING VALVE
3W	3-WAY MODULATING VALVE
TV	1/2"+4"(D) THERMOWELL C/W 1/2" BUSHING X 1/2" PLUG
XXX.X	FLOOR ELEVATION ABOVE LEVEL
XXX.X	FLOOR ELEVATION TAG LEVEL
XXX.X	HEADROOM (FLOOR TO U/S HEIGHT)

NO.	DATE	BY
1	RE-ISSUED FOR PERMIT	E.P.
0	RE-ISSUED FOR PERMIT	E.P.
0	ISSUED FOR PERMIT	E.P.
NO.	DESCRIPTION	BY

THARK VOID ALL PRINTS DATED PREVIOUS TO FINAL DATE ABOVE

REVISIONS

CONTRACTOR MUST CHECK AND VERIFY ALL DIMENSIONS AND CONDITIONS ON THE JOB AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK. THIS DRAWING IS THE PROPERTY OF THE ENGINEERS AND MUST BE RETURNED UPON COMPLETION OF THE WORK.

DRAWINGS ARE NOT TO BE SCALED

@1/8/14

178 West Beaver Creek Road, Unit 31
Richmond Hill, Ontario L4B 3M1
Tel: 905 882-8445
Fax: 905 882-8441

DRAWING TITLE:
14/F
MECHANICAL LAYOUT

PROJECT TITLE:
SQ ALEXANDRA PARK
BLOCK 11
38 CAMERON STREET
TORONTO ONTARIO

DRAWN BY:	CHECKED BY:	SCALE:
G.S.	E.P.	1:50
DATE:	PROJECT NUMBER:	DRAWING NUMBER:
FEB. 13	1313	M-32 OF 43

Drawing name: \\CADSERVER\Current Dwg's\13\1313 - Alexandra Park\DWG\13-1313M - 3D\14F PLAN - MECHANICAL LAYOUT.dwg Printed: Sep 09, 2014 - 9:50am