

**FINISHES SCHEDULE**

<b>ACT#1</b>	<b>Corridor Ceiling Tile</b> CGC Fireline EBF ceiling grid system, 6' cross base, flat white, grid edge: FLB, wall molding detail: MS17A, CGC Line Chromagel ceiling tile, 2'x4' x 3/4" - 62a, white. Supplier: CGC	<b>PAINT #9</b>	<b>(Lobby General)</b> Refer to Paint #1.	<b>TILE #6</b>	<b>(Kitchen Floor)</b> 24"x24" porcelain tile, Metal Glass, Steel Wood, #M02034MGL02, grout TBD. Install as per manufacturer's directions. Refer to floor finish plan for location. Supplier: Division 9 Contact: Mary Kourou 905.789.3786 x244
<b>BASE #1</b>	<b>100mm Tile Base</b>	<b>PAINT #10</b>	<b>(Suite Entry/typ doors and Frames)</b> Dulux, Forest Black #30YY 10038, latex, flat finish. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #7</b>	N/A
<b>BASE #2</b>	<b>100mm MDF Applied Base</b>	<b>PAINT #11</b>	<b>(Typ Corridors Base)</b> Dulux, Forest Black #30YY 10038, flat finish. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #8</b>	<b>(Mail Room Flooring)</b> 60x120cm porcelain tile, Stone Project, Grey, Falds Naturale, 60x120, grout colour TBD. Refer to floor finish plan for location. Supplier: Stone Tile
<b>BASE #3</b>	<b>100mm MDF Finish Base</b>	<b>PAINT #12</b>	<b>(Fitness Room Base)</b> Dulux, Song Porcelain #00NN 83'000, latex, flat finish. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #9</b>	<b>(Prog Management Kitchen/Admin)</b> Porcelain tile, Versus, Ice Natural #VEIC1224, 12"x24", grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location. Supplier: Centura
<b>BASE #4</b>	<b>75mm Tile Base</b>	<b>PAINT #13</b>	<b>(Changeroom Water Closet Walls)</b> Refer to Paint #8.	<b>TILE #10</b>	<b>(Whirlpool Room Flooring)</b> Refer to Tile #3.
<b>BASE #5</b>	<b>100mm Tile Base w/ Tile Trim #1</b>	<b>PAINT #14</b>	<b>(Typ Corridor Utility doors - Electrical Closet, Garbage Chute, Exit Stairs)</b> Dulux, Stratosphere, #40YV 73' 028, latex, semi gloss finish. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #11</b>	<b>(Lobby Recessed Base)</b> Unicolor Super Black Polished BY LIN BLK 1224, out to size per detail. Install as per manufacturer's directions. Refer to floor finish plan for location. Supplier: Olympia Tile
<b>BASE #6</b>	<b>100mm Metal Base</b>	<b>PAINT #15</b>	<b>(HM Door Frame paint to match the walnut wood surround for the common area doors)</b> Benjamin Moore CC - 514 Hiking Trail. Refer to Typical Details	<b>TILE #12</b>	<b>(Changerooms, Showers)</b> Mosaic tile, Quebec, Dark Grey FS, 2"x2", unglazed, #00.CD.STR.0202.FS Refer to floor finish plan for location. Supplier: Olympia Tile
<b>BASE #7</b>	<b>50mm Recessed Base for Tile #11</b>	<b>PAINT #16</b>	<b>(Amenity Fitness, Utility Walls)</b> Benjamin Moore Simply White, 2143-70, latex semi gloss finish. Refer to elevations and wall finishes plan for location.	<b>TILE #13</b>	<b>(P Level Elevator Lobby Walls)</b> 12x24" porcelain tile, Montecassino Matte, vein out, Grey, natural finish, #2S MC GR Y 1224.MT.VC. grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location. Supplier: Olympia Tile
<b>BASE #8</b>	<b>50mm Cove Base</b> (for Quebec Series unglazed mosaic to match adjacent floor tile)	<b>PAINT #17</b>	<b>(Railing finish in stairwell from P level to ground floor &amp; from 2nd floor to PH level)</b> to match paint #7	<b>TILE #14</b>	<b>(P Level Elevator Lobby Flooring)</b> 12x24" porcelain tile, Evolve Night Black #VA.EV.NHT.1224, grout colour TBD. Install as per manufacturer's directions. Refer to floor finishes plan for location. Supplier: Olympia Tile
<b>CARPET#1</b>	<b>(Prog Management Office)</b> Carpet Tile, Stack 9 #04332, Colour: Lustrous #75001, 24"x24" Unidirectional Installation, 100% Solution Dyed Supplier: Tandus Flooring Contact: Thomas Jackson 416-768-8939	<b>PAINT #18</b>	<b>(Janitor room Door)</b> Benjamin Moore, HC-166,	<b>TILE #15</b>	<b>(Staff WC Changeroom Floor)</b> 12x24" porcelain tile, Evolve, Color: Night (Black), natural finish, #VA.EV.NHT.1224, grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location. Supplier: Olympia Tile
<b>CARPET#2</b>	<b>(Theatre)</b> Broadloom Carpet, Data Stream #A0036, Colour: Black Metallic #01902, 12' 6" (381 cm) wide, Dunes nylon, solution dyed Supplier: Tandus Flooring	<b>PAINT #19</b>	<b>(FCU Access Door in Kitchen)</b> Dulux 30YY 11070, (A1601) Burnwood. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #15a</b>	<b>(Staff WC Changeroom Cove Base)</b> Quebec Series unglazed mosaic 2x2 cove base, to match Tile #13 (colour TBD) Supplier: Olympia Tile
<b>CARPET#3</b>	<b>(Corridors, Typical)</b> Broadloom Carpet, Trace #44053, Colour: Lead Mark #01910, 100% Solution Dyed Supplier: Tandus Flooring	<b>P.LAMB#1</b>	<b>(Prog Management Kitchen/Admin)</b> Arborte, Cordova Brown, #5-508-SR. Refer to elevations for location. Supplier: Wilsonart Contact: Janet Bascoe-Spencer 905.566.1255 x5731	<b>TILE #16</b>	<b>(Whirlpool Room Walls)</b> 150x90cm porcelain tile, Stone&Co, Colour: Bright Grey, natural finish, grout colour TBD. Install as per manufacturer's directions. Refer to elevations for location. Supplier: Stone Tile
<b>CARPET#4</b>	<b>(Corridors, Typical Accent)</b> Broadloom Carpet, Abaca 51050, Colour: Ostrich 00809, 100% Solution Dyed Supplier: Tandus Flooring	<b>P.LAMB#2</b>	<b>(Prog Management Kitchen/Admin)</b> Arborte, Fumed American Elm, #W-468 EV. Refer to elevations for location. Supplier: Wilsonart	<b>TILE #17</b>	<b>(Elevator Lobby Wall Ground Floor)</b> Changed to Glass #2 Supplier: Stone Tile
<b>GLASS#1</b>	N/A	<b>P.LAMB#3</b>	<b>(Concierge Millwork / Parcel Storage)</b> Arborte, Cordova Brown, #5-508-SR. Refer to elevations for location. Supplier: Wilsonart	<b>TILE #18</b>	<b>(Typ Corridor Walls @ Elevator)</b> 150x90cm porcelain tile, Stone&Co, Colour, polished finish, grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location. Supplier: Stone Tile
<b>GLASS#2</b>	<b>(Lobby Wall Paneling)</b> 1/4" or thickness as required. Back painted glass, star-fine, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: NGI Designer Glass	<b>P.LAMB#4</b>	<b>(Party Room Island)</b> Arborte, Cordova Brown, #5-508-SR. Refer to elevations for location. Supplier: Wilsonart	<b>TILE #19</b>	<b>(Public Barrier Free Washroom Walls)</b> 3"x10" ceramic tile, Liverpool, col: Portland, glossy grout TBD. Install as per manufacturer's directions. Refer to floorwall finishes plan for location. Ensure grout lines align as per floor finishes plan/elevations. Supplier: Cera Gres Contact: Jessica Caro 416-298-3553
<b>GLASS#3</b>	<b>(Dining Room Party Room)</b> 1/4" or thickness as required, NCM#8 Bronze Silk, star-fine, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: NGI Designer Glass	<b>RUBBER #1</b>	<b>(Gym Floor)</b> Johnsonite Triumph, 610mm x 610mm x 9.5mm, Colour: #29 Moon Rock, square edge tiles, laminated surface texture (SMH). Install as per manufacturer's directions. Refer to floor finish plan for location. Supplier: Johnsonite Contact: Tom Joyce 905.566.0061	<b>TILE #20</b>	<b>(Changerooms - Cove Base)</b> Quebec Series unglazed mosaic 2x2 cove base, to match Tile #3 (colour TBD) Supplier: Olympia Tile
<b>GLASS#4</b>	<b>(Lobby Fireplace Wall)</b> 1/4" or thickness as required, NCM Black Mirror, star-fine, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: NGI Designer Glass	<b>SP. MATERIAL #1</b>	<b>(Lobby Column Covers)</b> 16ga Black hairline stainless steel. Refer to elevations for location. Supplier: Formuovo	<b>TILE #21</b>	<b>(Barrier Free Washroom Mural)</b> Bisazza mosaic mural, 10cm x 10cm, Stature shading blend, colour: Gelsomino. Install as per manufacturer's directions. Refer to floorwall finishes plan for location. Ensure grout lines align as per floor finishes plan/elevations. Supplier: Stone Tile Stone Tile
<b>GLASS#5</b>	<b>(Whirlpool glass wall into gym, glass doors)</b> 1/2" or thick as required frosted glass. Supplier: Toro Aluminum	<b>SLAB#1</b>	<b>(Millwork, Concierge Desk)</b> Cipolino, polished Supplier: Ciot Contact: Aaron Huynh 416.739.8000 x8888	<b>TILE #22</b>	<b>(Garbage Room Floor)</b> 50mm x 50mm Quebec Series Black FS, Grout Flexite, Col: Charcoal. Install as per manufacturer's directions. Refer to floorwall finishes plan for location. Ensure grout lines align as per floor finishes plan/elevations. Supplier: Olympia
<b>HARDWOOD#1</b>	<b>(Party Room)</b> Kerwood Originals, 7.5" wide, engineered plank floor Col: Oak Silver Creek Random plank installation, direct glue down. Supplier: Metropolitan Hardwood Floors	<b>SLAB#2</b>	<b>(Millwork, Concierge Desk)</b> Nero Voda, cross out, honed. Supplier: Ciot	<b>TILE #23</b>	<b>(Garbage Room Walls)</b> 300mm x 600mm porcelain tile, Eiger Antracite, Grout Flexite, Col: Charcoal. Install as per manufacturer's directions. Refer to floorwall finishes plan for location. Ensure grout lines align as per floor finishes plan/elevations. Supplier: Ciot
<b>HARDWOOD#2</b>	N/A	<b>SLAB#3</b>	<b>(Lobby, Elevator surround)</b> N/A Supplier: Ciot	<b>TILE #24</b>	<b>(Ground Floor Interior Whirlpool)</b> 1" x 1" unglazed porcelain tile, Quebec Series, col: black Refer to floor finish plan for location. Supplier: Casarstone Contact: Michelle Greco 416-478-6949
<b>MELAMINE #1</b>	<b>(Amenity Kitchen)</b> Living Art, European Wood Surface #LW-3078 or approved alternative. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: By Kitchen Manufacturer/Living Art Contact: Paris Kitchens	<b>SLAB#4</b>	<b>(Amenity Kitchen Counter, Party Room Bar Table)</b> 1/2" Slab, Casarstone #5110 Alpine Mist, edges to be polished. Supplier: Casarstone Contact: Michelle Greco 416-478-6949	<b>TILE #25</b>	<b>(Ground Floor Interior Whirlpool Noosing)</b> 1" x 1" unglazed porcelain tile, Quebec Series, col: arctic white Refer to floor finish plan for location. Supplier: Olympia Tile
<b>METAL #1</b>	<b>Blackened Stainless Steel</b> , gauge to be confirmed by fabricator. Refer to elevations for location. Supplier: By Millwork/Option 3 Display Contact: Form Nuovo Tony Krlich 416-258-9711	<b>SLAB#5</b>	<b>(Prog Management Kitchen/Admin)</b> 1/2" Slab, Casarstone #2141 Bizzard, edges to be polished. Supplier: Casarstone	<b>TILE #26</b>	<b>(Ground Floor Fitness Wall Tile)</b> 2"x8" glazed ceramic tile, Colour and Dimension Series, col: arctic white Refer to floor finish plan for location. Supplier: Olympia Tile
<b>METAL #2</b>	<b>(Party Room Divider Screen)</b> Steel coil mesh, antique bronze finish, 18-20 gauge. Refer to elevations for location. Supplier: Sunbrite Contact: 800-999-2545	<b>SLAB#6</b>	<b>(Changeroom)</b> 1/2" Slab, Casarstone #4003 Sleek Concrete, edges to be polished. Supplier: Casarstone	<b>TILE #27</b>	<b>(Party Room &amp; Theatre Kitchen Counter)</b> 1/2" Slab, Paragon Black, polished, edges to be polished. Supplier: Ciot
<b>METAL #3</b>	<b>(Party Room Bar Table)</b> Brass to match Chemical #225 Stately Brass, ga. to be confirmed by fabricator. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Lacquered, scratch resistant finish. Supplier: Lido Construction Inc Contact: Lucia Nu 905-660-0410	<b>SLAB#7</b>	<b>(Party Room Bar Counter)</b> 1/2" Slab, same as slab #7 Supplier: Ciot	<b>TILE TRIM #1</b>	<b>(Exposed Wall Tile Edges)</b> Schuler Joly, Brushed Nickel, size to suit tile.
<b>METAL #4</b>	<b>(Fitness Room - Glazing Shoe)</b> Satin Chrome from standard offering. Supplier: Glazing Supplier	<b>SLAB#8</b>	<b>(Lobby Flooring)</b> 60x120cm porcelain tile, Stone Project, Grey Falds Naturale, 60x120, grout colour TBD. Refer to floor finish plan for location. Supplier: Stone Tile Contact: Debra Rubin 416-515-9000 x245	<b>TILE TRIM #2</b>	<b>(Laminato to Laminato)</b> Schuler Schiene, Brushed Nickel, size to suit laminate floor.
<b>METAL #5</b>	<b>(Entrance, Metal Shroud @ sinks, Elevator Cabs, P1 and 14th Floor Elevator Doors/Frames)</b> Stainless Steel, thickness as required. Supplier: Millwork	<b>TILE #2A</b>	<b>(Lobby Flooring Accent)</b> 20x120cm porcelain tile, Stone Project, Grey Falds Naturale, grout colour TBD. Refer to floor finish plan for location. Supplier: Stone Tile	<b>WALLCOVERING #1</b>	<b>(Corridors)</b> Vinyl Wallcovering, Custom Type II wallcovering based on Vessom 05 - Tempe #766.12. Refer to wall finishes plan and elevations for location. Supplier: Metro Wallcovering Contact: Charley Binder 905.738.7461
<b>METAL #6</b>	<b>(Throughout, Elevator Doors and Frame on Grd Flr)</b> XL Black Hairline Stainless Steel Supplier: Form Nuovo	<b>TILE #2B</b>	<b>(Lobby Flooring Accent)</b> 20x120cm porcelain tile, Stone Project, Grey Falds Lappato, grout colour TBD. Refer to floor finish plan for location. Supplier: Stone Tile	<b>WALLCOVERING #2</b>	<b>(Party Room)</b> Vinyl Wallcovering, Vessom 05 Tessera 770.11, 52" wide, 20oz. Type II, Class A. Refer to wall finishes plan and elevations for location. Supplier: Metro Wallcovering
<b>MIRROR#1</b>	N/A	<b>TILE #3</b>	<b>(Changerooms Flooring)</b> 15x90cm porcelain tile - cut down to 15x15cm square format, Stone&Co, Colour: Bright Grey, natural finish, grout colour TBD. Install as per manufacturer's directions. Refer to floor finish plan for location. Supplier: Dulux Contact: Debra Rubin 416.515.9000 x299	<b>WALLCOVERING #3</b>	<b>(Dining Room Accent)</b> Custom Vinyl Mural Wallcovering, image/graphic to be selected by designer and printed on vinyl substrate, Type II, Class A. Refer to wall finishes plan and elevations for location. Supplier: Metro Wallcovering
<b>MIRROR#2</b>	<b>(Fitness)</b> 1/4" or thickness as required, clear mirror, tempered. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: NGI Designer Glass	<b>TILE #4</b>	<b>(Changeroom Walls)</b> 4x16" ceramic tile, Colour & Dimensions Collection, Arctic White Bright, #0T CD ARW 0416 BR, grout TBD. Install as per manufacturer's directions. Refer to wall finishes plan for location. Ensure grout lines align as per wall finishes plan. Supplier: Dulux	<b>WALLCOVERING #4</b>	<b>(Dining Room Accent)</b> Custom Vinyl Mural Wallcovering, image/graphic to be selected by designer and printed on vinyl substrate, Type II, Class A. Refer to wall finishes plan and elevations for location. Supplier: Metro Wallcovering
<b>FEDMATH#1</b>	<b>(All Vests/benches)</b> Construction Specialist's Ordline G6. Install according to LEED requirements, as shown on floor finishes plan. Install flush to adjacent floor finishes. Supplier: Construction Specialist's	<b>TILE #5</b>	<b>(Changeroom Water Closet Walls)</b> Dulux, Zeppelin, #30YY 46' 030, latex, flat washable finish. Refer to elevations and wall finishes plan for location.	<b>WALLCOVERING #5</b>	<b>(Amenity Dining Room &amp; Kitchen)</b> Vinyl Wallcovering, Koroseal, Montage, Café Noir #721-85, 54" wide, Type II, Class A. Refer to wall finishes plan and elevations for location. Supplier: Metro Wallcovering
<b>PAINT#1</b>	<b>(General Walls, Throughout)</b> Dulux, Song Porcelain #00NN 83'000, latex flat washable finish. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #6</b>	<b>(Staff WC Shower Changeroom Walls)</b> Same as Tile #4	<b>WALLCOVERING #6</b>	<b>(Theatre)</b> Vinyl Wallcovering, Colour and Design, Chava Gini, CD2-00C-45, Black Mica, 54" wide, Type II, Class A. Refer to wall finishes plan and elevations for location. Supplier: Olympia Tile Contact: Lucy Capobianco 416.785.9555 x254
<b>PAINT #2</b>	<b>(Ceiling, Throughout)</b> Dulux, Song Porcelain #00NN 83'000, latex, flat finish. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #7</b>	<b>(Dining Room - Wall and Base)</b> Dulux, Designer Grey, 50YY 63041, latex, semi gloss for base and eggshell finish for walls. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>WALLCOVERING #7</b>	<b>(Gr Floor Public Spaces)</b> Refer to Wallcovering #3.
<b>PAINT #3</b>	<b>(P Mgmt Office Wall and Base)</b> Dulux, Designer Grey, 50YY 63041, latex, semi gloss for base and eggshell finish for walls. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #8</b>	<b>(Staff WC Shower Changeroom Walls)</b> Same as Tile #4	<b>WALLCOVERING #8</b>	<b>(Gr Floor Fitness)</b>
<b>PAINT #4</b>	<b>(Parking Level Elevator Doors and Frames)</b> Dulux, Forest Black #30YY 10038, latex, semi gloss finish. Refer to elevations and wall finishes plan for location. Supplier: Dulux	<b>TILE #9</b>	<b>(Staff WC Shower Changeroom Walls)</b> Same as Tile #4		

<b>WALLCOVERING #9</b>	<b>(Gr Public Washroom)</b> Vinyl Wallcovering, Colour and Design, Canton Rainalk, CD2-CTR-13, Clean Slate, 54" wide, Type II, Class A. Refer to wall finishes plan and elevations for location. Supplier: Metro Wallcovering
<b>WOOD#1</b>	<b>(Party Room Millwork - Throughout)</b> TAY (KOTI) 04.005 veneer, clear coat 10% sheen of high quality urethane to be applied for protection, 30lbs as required. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: By MillworkerMaterials Inc. Contact: Leonardo Fiaschi 201.988.0191
<b>WOOD#2</b>	<b>(Lobby Millwork Throughout - Fin Detail)</b> Walnut, flat cut, M-23126, veneer, oiled finish. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: By MillworkerMaterials Inc.
<b>WOOD#3</b>	<b>(Typ Suite Door Surrounds)</b> Walnut, flat cut, M-23126, veneer, oiled finish. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: By MillworkerMaterials Inc.
<b>WOOD#4</b>	<b>(Lobby Millwork - Ceiling)</b> Koroseal Actor Series Wood wallcovering, Walnut, flat cut, veneer applied directly onto drywall ceiling. Flame Spread rating: 0. Class A fire rating. Supplier to create install pattern. Block material as required. Contractor to provide sample for designer review and approval prior to fabrication. Refer to elevations for location. Supplier: Metro Wallcovering Contact: Charley Binder
<b>WINTER MATTING#1</b>	<b>(Lobby, P Levels, 9th Flr - To Outdoor Amenity)</b> VI-Floor, Super Series, Col: 1172, Solution dyed Polypropylene fibers Total Thickness: 12.5mm (0.5") Supplier: VI Floor Contact: Bob Dobson 416.521.9014
<b>FABRICS</b>	<b>(Dining Room Drapery)</b> FABRICUT CONTRACT, TAJMMML-L, ONYX, 117"WIDE, VERTICAL REPEAT 100% POLYESTER
<b>FABR#1</b>	<b>(Party Room Kitchen)</b> ALENDEL CONTRACT, CASINO, CHROME, 122"WIDE, NO REPEAT 100% POLYESTER

**PLUMBING SCHEDULE**

<b>P1 - TOILET</b>	<b>(Ground Flr WC / 2nd floor change room, 6th floor changeroom, Ground Floor Fitness)</b> Kohler HighCliff toilet bowl K-4368, white finish, c/w Lustra open front seat K-4369; col: White. Exposed toilet flushometer - 1.28 gpf, K-150-16, polished chrome finish. Refer to Furniture & Power plan for locations Supplier: Kohler Contact: Arnel Go 416-716-0536
<b>P2 - BASIN</b>	<b>(Ground Floor WC/P1 WC)</b> American Standard Wheelchair Users Lavatory, Vitreous china, 9140.047 Center Hole Only. 20"x20" Colour: White Supplier: American Standard Contact:
<b>P3 - FAUCET</b>	<b>(Ground Floor WC)</b> Hansgrohe Metris S Single Hole Faucet c/w pop up, 31050001, Chrome Finish. Install according to OBC requirements for Barrier Free. Supplier:
<b>P4 - SINK</b>	<b>(Ground Floor Changerooms)</b> White vitreous china ring counter sink P-5-105, 16" x16" x 6-3/4", c/w recommended drain. Refer to Furniture & Power plan for locations. Supplier: Cantrio Concepts
<b>P5 - SHOWER HEAD</b>	<b>(Ground Floor Changerooms)</b> Hansgrohe, Raindance Connected Shower System, wall mounted shower head and hand shower, model #27164001, chrome finish. Complete with required rough-ins, wall outlets and temp control trim. Supplied By:
<b>P6 - FAUCET</b>	<b>(Ground Floor Changerooms)</b> Hansgrohe Metris S Faucet # 31163001 with Preset Temperature control. Battery operated (included). Chrome Finish. Supplier:
<b>P7 - SINK</b>	<b>(Ground Floor Amenity Bar)</b> Stainless steel undermount sink KSS-003, c/w mtg hardware and all parts. Refer to Furniture & Power plan for locations. Supplier: Cantrio Concepts
<b>P8 - SINK</b>	<b>(Ground Floor Amenity Kitchen)</b> Stainless steel undermount sink KSS-005, 18"x23"x10.5" c/w mtg hardware and all parts. Refer to Furniture & Power plan for locations. Supplier: Cantrio Concepts
<b>P9 - FAUCET</b>	<b>(Ground Floor Amenity Kitchen)</b> Blanco Cucina Mtr Pull Down Kitchen Faucet, Item No.401567, pull out single spray, swivel spout, chrome finish, 1.8gpm. Refer to Furniture & Power plan for locations.
<b>P10 - FAUCET</b>	<b>(Ground Floor Bar)</b> Blanco Cucina Mtr Pull Down Kitchen Faucet, Item No.401567, pull out single spray, swivel spout, chrome finish, 1.8gpm. Refer to Furniture & Power plan for locations.
<b>P11 - LINEAR FLOOR DRAIN</b>	<b>(Amenity Showers)</b> Infinity drain, S-AS 65, complete kit, site specific. Size per plan. Polished Stainless finish. Complete with all necessary components. Refer to Furniture and Power plan for locations. Consult with landscape architect. Supplier: Infinity Drain
<b>P12 - SINK</b>	<b>(P1 Level Kitchenette)</b> Stainless steel undermount sink KSS-2018, 20"x18"x8" c/w sound dampening pads, hardware and all parts. Refer to Furniture & Power plan for locations Supplier: Cantrio Concepts
<b>P13 - FAUCET</b>	<b>(P1 Level Kitchenette)</b> American Standard Collina Single Control kitchen faucet, pull down spray, chrome finish, 4717.300, 1.8gpm. Refer to Furniture & Power plan for locations.
<b>P14 - BOTTLE FILLING STN</b>	<b>(Fitness Area Ground Floor)</b> Ebay C2H20 Bottle Filling Station with B-Level EZ Cooler Model LZSTL8W9. Refer to Furniture & Power plan for locations. Supplier: Elkay
<b>P15 - SHOWER HEAD</b>	<b>(P1 Level Changeroom)</b> American Standard, Serin Shower System Kit, model # 2064.724, 3 function adjustable hand shower, hose, wall spray, and slide bar, chrome finish. Complete with required rough-ins, control valves, trim kit and accessories. Supplied By: American Standard Contact: (647)201-6633
<b>P16 - BASIN</b>	<b>(P1 Level Changeroom)</b> Same as P2
<b>P17 - FAUCET</b>	<b>(P1 Level Changeroom)</b> American Standard Serin Single hole faucet, chrome finish, 2064.101, with pop up drain, 1.8gpm. Refer to Furniture & Power plan for locations.
<b>P18 - BARRIER KIT</b>	<b>(Ground floor) P1 barrier free washroom)</b> Cabano 75101 Build a Shower Site Shower rail kit, Incl Bar, hose and hand shower, Chrome. Mounting height according to OBC barrier free requirements.
<b>P19 - N/A</b>	
<b>P20 - JANITOR SINK</b>	<b>(Ground floor)</b> Model stone mop service basin, MSB2424, 24"x24"x10" deep, refer to furniture and power plan for location
<b>P21 - JANITOR SINK FAUCET</b>	<b>(Ground floor)</b> Delta sink faucet wall mount, Model no: 2879, refer to furniture and power plan for location

<b>E1 - INTEGRAL SOAP DISPENSER</b>	<b>(washrooms)</b> Stern Engineering Commercial Electronic smart touch free soap dispenser. Ref # 235900 Supplier: Stern Engineering
<b>E2 - TOWEL DISPENSER</b>	<b>(washrooms)</b> Bobrick surface mount dispenser/disposal fixture B-43699, stainless steel satin finish Supplier: Citywide door and hardware
<b>E3 - TOILET TISSUE DISPENSER</b>	<b>(washrooms)</b> Bobrick surface mount multi roll toilet tissue dispenser, model B-2888 and recessed model B-3888, stainless steel satin finish Supplier: Citywide door and hardware
<b>E4 - FEMININE NAPKIN DISPOSAL</b>	<b>(washrooms)</b> Bobrick recessed feminine napkin disposal model#B-353 stainless steel satin finish Supplier: citywide door and hardware
<b>E5 - GRAB BARS</b>	<b>(washrooms)</b> Bobrick grab bar system B-5898, B-5806 series, complete with concealed mounting, contractor to ensure system complies with OBC, stainless steel finish Supplier: citywide door and hardware
<b>E6 - HOOK</b>	<b>(washrooms)</b> Bobrick surface mounted robe hook model#B-6717 stainless steel satin finish, refer to plans for location Supplier: Citywide door and hardware
<b>E7 - MAILBOXES</b>	<b>(Mailroom)</b> Riopel, model 4500-D192, rear loading horizontal mailboxes, refer to elevation for location Supplier: Riopel Contact: Order desk 1-514-934-0385
<b>E8 - FRIDGE</b>	<b>(Party room Kitchen)</b> 24" integrated refrigerator, Blomberg BFRB 1050 FFBI. Supplier: Appliance Canada John Oulahan 905-660-2424
<b>E9 - DISHWASHER</b>	<b>(Party room Kitchen)</b> 24" fully integrated dishwasher, Blomberg DBS100. Supplier: Appliance Canada
<b>E10 - MICROWAVE</b>	<b>(Party room kitchen)</b> Panasonic NN-S7655 Supplier: Appliance Canada
<b>E11 - ENTERPHONE</b>	<b>(entry)</b> By client
<b>E12 - LOCKERS</b>	<b>(Locker Room)</b> Hadrian "Emperor" Locker System, double tier, 72" high x 12" wide x 12" deep, col: Dove/steel, 828 Supplier: Hadrian Contact: Order Desk/ 905- 333-0300
<b>E13 - WATER FOUNTAIN</b>	<b>(Exercise Room)</b> Refer to P14 for spec.
<b>E14</b>	N/A
<b>E15 - TV</b>	<b>(Dining Room)</b> 46" By client
<b>E16 - TV</b>	<b>(Bar)</b> 46" TV mounted behind mirrored wall paneling, TBD
<b>E17 - TV</b>	<b>(Party Room)</b> 65", by client
<b>E18 - B.F. Mirror</b>	<b>(B.F washroom - P1 Level, 9th Floor)</b> Bobrick B293 1836, fixed position tilt mirror Supplier: Citywide door and hardware
<b>E19 - TBD</b>	
<b>E20 - Photocopier</b>	<b>(Management Office)</b> By client
<b>E24 - Warming Drawer</b>	<b>(Kitchen)</b> Porter and Charles WD60-14 24" stainless steel warming drawer, 5.5" high Supplier: Appliance Canada
<b>E25 - Warming Drawer</b>	<b>(Kitchen)</b> Porter and Charles WD60-21 24" stainless steel warming drawer, 8.2" high Supplier: Appliance Canada
<b>E26 - Elec Fireplace</b>	<b>(Dining Room)</b> Dimplex IgniteXL XLF50
<b>E27 - Whirlpool</b>	<b>(Changerooms)</b> Custom Concrete Whirlpool, with jets, as per pool supplier specifications. Supplier: Advanced Commercial Pool and Spa
<b>E28 - WALL MNT SOAP DISPENSER</b>	<b>(P1 and 9th Floor Washrooms, GF Mens &amp; Womens BF washrooms)</b> Bobrick Contura series recessed soap dispenser/Automatic Wall Mounted Foam Dispenser-Model B-2013, chrome finish Supplier: Citywide Door & Hardware
<b>E29 - UNDER COUNTER FRIDGE</b>	<b>(Prog Management/Bar Area)</b> Panel ready - 24" under counter fridge, Marvel ML24BR3FLP, handing as per elevation. Supplier: Appliance Canada
<b>E30 - ELEC FIREPLACE</b>	<b>(Lobby)</b> Dimplex IgniteXL XLF100
<b>E31 - COUNTER SOAP DISPENSER</b>	<b>(Ground Floor Washrooms/ Change Rooms)</b> Bobrick Model B-6263

**DO NOT SCALE DRAWINGS.**

CONTRACTOR MUST VERIFY ALL DRAWINGS, DIMENSIONS, DETAILS AND SPECIFICATIONS, AND REPORT ANY DISCREPANCIES TO UNION 31 INC. BEFORE PROCEEDING WITH WORK. MATERIALS MAY NOT BE SUBSTITUTED WITHOUT WRITTEN APPROVAL FROM UNION 31 INC.  
ALL DRAWINGS AND SPECIFICATIONS ARE INSTRUMENTS OF SERVICE AND THE PROPERTY OF UNION 31 INC. WHICH MUST BE RETURNED AT THE COMPLETION OF THE WORK.

PRINTED: 18-Sep-17

ISSUED FOR AS-BUILT

01	31 MAY / 17	ISSUED FOR AS-BUILT	SV
NO.	DATE	COMMENTS	INI

REVISIONS:

PROJECT NAME:		<b>ALEXANDRA PARK MAIN BUILDING</b>	
BLOCK 11		ON, Canada	
PROJECT NO.:	13-949		
DRAWINGS:			
FINISHES SCHEDULE		PLUMBING & EQUIPMENT SCHEDULE	

DATE STARTED:	07 AUG / 13	DRAWING NO.:	
---------------	-------------	--------------	--