

DOOR SCHEDULE

Where Applicable:
 • All doors, frames, and hardware are Designer's suggestions only. Specifications are to be confirmed by the Architect and door supplier in accordance with applicable building codes.

TYPICAL	DESCRIPTION
801	(Suite Entry) 2135mm high solid core slab wood door for paint finish, hardware to be signature series, Detroit, satin chrome finish, complete with mortise lock assembly to match, provide standard peep hole, hinges, spring hinges, all in satin chrome finish, door frame to be softframe metal door framing complete with 10 minute fire rating, suite casing as per developers specification on unit side, refer to elevation for corridor side. **GF, 2F, and 13F will have 2440mm high suite entry door height to match interior suite doors. Supplier: Citywide Door and Hardware Tony Sanchez (905) 264-4401
	(Typical Floors - electrical closet door, mechanical doors, refuse doors) 2135mm high hollow core metal doors as per architects specifications, for paint finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN #626 finish (satin chrome), provide hinges, self closer all in satin chrome finish. **GF, 2F, and 13F will have 2440mm high door height to match suite entry doors. Supplier: Citywide Door & Hardware
	(Typical Exit Stairs) 2135mm high hollow core metal doors as per architects specifications, for paint finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN #626 finish (satin chrome), provide hinges, self closer all in satin chrome finish. **GF, 2F, and 13F will have 2440mm high door height to match suite entry doors. Supplier: Citywide Door & Hardware
PARKING LEVEL 2	
P201.1, P201.3	(P2 Elevator Lobby) 2135mm high aluminum door, complete with vision glass as per architect's specifications, for paint finish as per curtain wall finish, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges self closer all in satin chrome finish. Supplier: Citywide Door and Hardware
P201.2	(Elevator Lobby to Vestibule) 2135mm high 90 mm rated hollow core metal door, complete with vision lite as per architect's specifications, for paint finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges self closer all in satin chrome finish. Electronic strike TBD as per architects specification. Supplier: Citywide Door and Hardware
PARKING LEVEL 1	
P110.1, P101	(P1 Lobby Vestibules) 2135mm high aluminum door, complete with vision glass as per architect's specifications, for paint finish as per curtain wall finish (TBD), hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges self closer all in satin chrome finish. Supplier: Citywide Door and Hardware
P110.1, P110	(Elevator Lobby to Vestibule) 2135mm high 90 mm rated hollow core metal door, complete with vision lite as per architect's specifications, for paint finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges self closer all in satin chrome finish. Electronic strike TBD as per architects specification. Supplier: Citywide Door and Hardware
P117	(Staff Room) 2135mm high 90 mm rated hollow core metal door, complete with vision lite and sidelight as per architect's specifications, for paint finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges self closer all in satin chrome finish. Electronic strike TBD as per architects specification. Supplier: Citywide Door and Hardware
GROUND FLOOR	
131.1	CORRIDOR A TO EXTERIOR 2135mm high, as per architect's specifications.
133	CORRIDOR B (GARBAGE ACCESS) 2135mm high as per architect's specifications.
138	MAIL SORTING 2440mm high custom solid core wood door for wood finish and base as per wall finishes plan and elevations, concealed casing, hardware to be flush hidden door pull, satin chrome finish, provide CRIL concealed hold open door closers - concealed in transom, concealed Soss hinges, satin chrome finish. Ensure veneer matches exactly to adjacent wall paneling. Consult with millworker as required. Coordinate locking mechanism with Canada Post guidelines. Supplier: Citywide Door and Hardware
140.1	Omitted
140.2	CORRIDOR B 2440mm high 45 mm rated wood door & hollow metal frame, complete with vision lite as per architect's specifications, for wood veneer finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges self closer all in satin chrome finish. Electronic strike TBD as per architects specification. Supplier: Citywide Door and Hardware
141.1	EAST VESTIBULE INTERIOR SIDE Double glazed bi parting doors as per architect's specifications, hardware to be by Canadian builders Hardware. Supplier: Toro Aluminium
141.2	EAST VESTIBULE TO EXTERIOR Double glazed automatic bi parting breakaway storefront door with sidelights as per architect's specification. Supplier: Toro Aluminium
142.1	RESIDENTIAL LOBBY 2745mm high double glazed doors, as per architect's specifications, c/w exit hardware, electronic operator. Supplier: Citywide Door and Hardware
142.2	WEST VESTIBULE 2745mm high double glazed doors, as per architect's specifications, c/w exit hardware, electronic operator. Electronic strike as per architect's specification. Supplier: Citywide Door and Hardware
143A	FITNESS ROOM VFCU ACCESS DOOR 2440mm high wood door, type L, with louver, HM frame, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), as per architect's specification, finish as per wall finishes plan. Supplier: Citywide Door and Hardware
143B	FITNESS ROOM VFCU ACCESS 2440mm high custom millwork vertical fan coil unit access door with louver, HM frame, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), as per architect's specification, finish as per wall finishes plan. Refer to detail # 4102.4.1 Supplier: Citywide Door and Hardware
143C	FITNESS ROOM VFCU ACCESS 2440mm high custom millwork vertical fan coil unit access door with louver, HM frame, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), as per architect's specification, finish as per wall finishes plan. Refer to detail # 4102.4.1 Supplier: Citywide Door and Hardware
144	VESTIBULE 2440mm high 90 mm rated hollow metal door & frame, type A with no vision, for paint finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges, self closer all in satin chrome finish. Supplier: Citywide Door and Hardware
145.2	RESIDENTIAL BIKE STORAGE 2440 mm high 45 mm rated hollow core metal door, complete with vision lite as per architect's specifications, for paint finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges self closer all in satin chrome finish. Electronic strike TBD as per architects specification. Supplier: Citywide Door and Hardware
146	MEN'S CHANGEROOM VESTIBULE 2440mm high solid core wood door for wood veneer finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L), both sides, provide concealed self closer, strike plate, hinges satin chrome finish. Supplier: Citywide door & hardware
146A	MEN'S CHANGEROOM VESTIBULE Same as 146.
146B	MEN'S CHANGEROOM STEAM ROOM 2440mm high frameless frosted glass door with weather stripping. Refer to architect's specification.
147	MEN'S CHANGEROOM WC 2440mm high solid core wood door for wood finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L), provide self closer, strike plate, hinges, privacy seal (inside only), satin chrome finish, refer to elevation. Supplier: Citywide door & hardware
148	MEN'S WC BF 2440mm high solid core wood door for wood finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L), provide self closer, strike plate, hinges, privacy seal (inside only), satin chrome finish, refer to elevation.
149.1	MENS CHANGEROOM TO WHIRLPOOL SPA 2440mm high frameless glazed door, thickness as req'd, tempered as required, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L) to match elevation, back to back installation, provide patch fittings, pivot hinges all in satin chrome finish, rubber stripping to be used as required. Contact: Toro Aluminium
149.2	WOMEN'S CHANGEROOM TO WHIRLPOOL SPA 2440mm high frameless frosted glass door, thickness as required, tempered as required, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L) to match elevation, back to back installation, provide patch fittings, pivot hinges all in satin chrome finish, rubber stripping to be used as required. Contact: Toro Aluminium
150	JANITOR CLOSET IN WOMEN'S CHANGEROOM 2440mm high hollow core metal door for paint finish as per wall finishes plan, hardware to be lever style handles by Schlage, AL-Series Jupiter, satin chrome finish, provide self closer, strike plate, hinges, satin chrome finish.

151	WOMEN'S CHANGEROOM VESTIBULE 2440mm high solid core wood door for wood veneer finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L), both sides, provide concealed self closer, strike plate, hinges satin chrome finish. Supplier: Citywide door & hardware
151B	WOMEN'S CHANGEROOM STEAM ROOM 2440mm high frameless frosted glass door with weather stripping. Refer to architect's specification.
151A	WOMEN'S CHANGEROOM VESTIBULE Same as 151
152	WOMEN'S CHANGEROOM WC 2440mm high solid core wood door for wood finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L), provide self closer, strike plate, hinges, privacy seal (inside only), satin chrome finish, refer to elevation. Supplier: Citywide door & hardware
153	WOMEN'S CHANGEROOM BF WC 2440mm high solid core wood door for wood finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L), provide self closer, strike plate, hinges, privacy seal (inside only), satin chrome finish, refer to elevation. Supplier: Citywide door & hardware
154	CORRIDOR D TO FITNESS AREA 2700mm high frameless double clear glazed door, thickness as req'd, tempered as req'd, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide concealed self closer, strike plate, power assist H.A.S. Concealed automatic operator, refer to elevations. Supplier: Toro Aluminium
156	BARRIER FREE WC 2440mm high solid core wood door for wood finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L) (corridor side only), provide self closer, strike plate, hinges, privacy seal (inside only), satin chrome finish, refer to elevation. Supplier: Citywide door & hardware
157	BARRIER FREE WC 2440mm high solid core wood door for wood finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L) (corridor side only), provide self closer, strike plate, hinges, privacy seal (inside only), satin chrome finish, refer to elevation. Supplier: Citywide door & hardware
158	THEATRE 2440 mm high solid core wood door complete with flush concealed Soss hinges and provide concealed self closer, strike plate hardware to be Elmes full length pull # G999-01-130 P1925 (2135mm L), both sides, refer to elevation. Supplier: Citywide door & hardware
158A	THEATRE VFCU PANEL 2440mm high custom millwork vertical fan coil unit access frameless door panel with louver on piano hinges. Clip system to be similar to spec or a suitable alternate: Button Fix 2 supplied by Lee Valley. Finish as per wall finishes plan. Refer to detail # 4102.4.1 Supplier: Millworker
158C	THEATRE EQUIPMENT ROOM 2440mm high solid core wood door for paint finish as per wall finishes plan, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide self closer, strike plate, hinges, satin chrome finish. Supplier: Citywide door & hardware
159	CORRIDOR D ELECTRICAL CLOSET 2440mm high 60 mm rated wood door for wood finish per wall finishes plan, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide self closer, strike plate, hinges, satin chrome finish. Inset flush with corridor walls. Supplier: Citywide door & hardware
160.1	CORRIDOR C TO CORRIDOR A 2440mm high 45 mm rated wood door & hollow metal frame, complete with vision lite as per architect's specifications, for wood veneer finish as per wall finishes plan, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN#626 (satin chrome), provide hinges self closer all in satin chrome finish. Electronic strike TBD as per architects specification. Supplier: Citywide Door and Hardware
160.2	PARTY ROOM AMENITY ENTRANCE 2700mm high Type II frameless clear glazed pivot door with side lite, thickness as req'd, tempered as req'd, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide concealed self closer, strike plate, power assist, refer to elevations. Concealed strike in header. Glazing film by designer. Supplier: Toro Aluminium
161.1	CORRIDOR TO DINING ROOM 2440mm high solid core wood door for wood #1, hardware to be Elmes full length pull # G999-01-130 P1925 (1830mm L), both sides, satin chrome finish, provide concealed self closer, strike plate, hinges, satin chrome finish with no vision type A Supplier: Citywide door & hardware
161.2	KITCHEN TO DINING ROOM 2440mm high solid core wood door for wood #1, hardware to be Elmes full length pull # G999-01-130 P1925 (1830mm L), both sides, satin chrome finish, provide concealed self closer, strike plate, hinges, satin chrome finish with no vision type A Supplier: Citywide door & hardware
161A	DINING ROOM VFCU PANEL 2440mm high custom millwork vertical fan coil unit access frameless door panel with louver on piano hinges. Clip system to be similar to spec or a suitable alternate: Button Fix 2 supplied by Lee Valley. Finish as per wall finishes plan. Refer to detail # 4102.4.1 Supplier: Millworker
162	AMENITY KITCHENETTE 2440mm high solid core wood door for wood #1, hardware to be Elmes full length pull # G999-01-130 P1925 (1830mm L), both sides, satin chrome finish, provide concealed self closer, strike plate, hinges, satin chrome finish Supplier: Citywide door & hardware
162A	AMENITY KITCHENETTE VFCU 2440mm high wood door & frame, type T with louver, as per architect's specification Finish as per wall finishes plan. Supplier: Citywide Door and Hardware
163	AMENITY - PARTY ROOM EXIT TO TERRACE 2675 mm high, as per architectural specification.
163A	AMENITY PARTY ROOM VFCU 2440mm high wood door & frame, type T with louver, as per architect's specification finish as per wall finishes plan. Supplier: Citywide Door and Hardware
163B	AMENITY PARTY CLOSET 1.2 x 2440mm high wood doors by millworker to match cabinetry in party room bar. Supplier: Citywide Door and Hardware
164	PROPERTY MANAGEMENT OFFICE 2440mm high frameless clear glazed door, thickness as req'd, tempered as req'd, privacy film to be applied to glass- design to be determined by designer, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide concealed self closer, strike plate, full chrome finish, refer to elevations. Supplier: Toro Aluminium
166.1	MANAGEMENT OFFICE 2440mm high door for paint finish as per wall finishes plan, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide self closer, strike plate, hinges, satin chrome finish, refer to elevation. Supplier: Citywide door & hardware
166.2	MANAGEMENT OFFICE MECH. CL. 2440mm high hollow core metal door for paint finish as per wall finishes plan, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide self closer, strike plate, hinges, satin chrome finish. Supplier: Citywide door & hardware
167	KITCHEN / COPY 2440mm high solid core wood door for paint finish as per wall finishes plan, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide self closer, strike plate, hinges, satin chrome finish, refer to elevation. Supplier: Citywide door & hardware
167.1	KITCHEN/COPY ROOM VFCU ACCESS 2440mm high solid core wood door for paint finish as per wall finishes plan, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, lockset, provide strike plate, hinges, satin chrome finish, refer to elevation. Supplier: Citywide door & hardware
168	CACR ROOM 2440mm high 180 degree opening 90mm rated solid core slab wood pivot door for wood#2, HW frame, wood to be treated for fire rating, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN #626 finish (satin chrome), provide concealed Soss hinges, self closer all in satin chrome finish, electronic strike TBD as per architect's specifications, refer to elevations. Supplier: Citywide door & hardware
169	PARCEL ROOM 2440 mm high solid core slab wood door for wood#2, HM frame, wood to be treated for fire rating, hardware to be Schlage Architectural hardware, lever style pulls, S Series model Jupiter, IN #626 finish (satin chrome), provide concealed Soss hinges, self closer all in satin chrome finish, electronic strike TBD as per architect's specifications, refer to elevations. Supplier: Citywide door & hardware
172.2	GROUND FLOOR RESIDENTIAL GARBAGE 2440mm high 90 mm rated hollow core metal door for paint finish as per wall finishes plan, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, provide self closer, strike plate, hinges, satin chrome finish. Supplier: Citywide door & hardware
173.1	RESIDENTIAL MOVING 2440mm high 45 mm rated hollow core metal door for paint finish as per wall finishes plan, hardware to be lever style handles by Schlage, s-series Jupiter, satin chrome finish, provide self closer, strike plate, hinges, satin chrome finish. Supplier: Citywide door & hardware
935	9th FLOOR BF WC 2135mm high solid core wood door for wood finish as per wall finishes plan, hardware to be Elmes full length pull #G999-01-130 P1925 (1830mm L) to match elevation, back to back installation, provide patch fittings, pivot hinges all in satin chrome finish, rubber stripping to be used as required. Supplier: Citywide door & hardware

LIGHTING AND ELECTRICAL LEGEND

	TYPE A (Throughout) Recessed rectangular directional down light fixture Eurasole TL1 Trimmable Recessed LED w/ driver Size: 4" x 4" Lamp: 3 x 9w LED, warm white 3000K Finish: White Specification: # TE121LED-02 Suitable housing as required. Plaster kit as required. Refer to RCP for location. Supplier: Litemode Contact:
	TYPE B (Lobby, Beside Fireplace) Pendant Vibra Slim one light pendant or Approved Equal Size: 30.25" x 1.6" x 6-11/16" canopy Lamp: 1x3w LED Finish: Black Specification: Slim 0920 Suitable housing as required. Refer to RCP for location.
	TYPE C (Lobby Lounge) Concentric ring chandelier Paul Leonard Halo Chandelier - 3 Rings Rd and Hll 42" dia x 34" 12 Week Lead Time** Blackened Steel Finish Drop length TBD as per architect's specification. Supplier: Light Form
	TYPE D (Throughout) Same as Type A, to be amended and adjusted on site with designer.
	TYPE E (Cove Lighting Throughout) InvalLED Pro 2 High Output Tape Light LED TX2430-5-WT 4w per foot, 90 CRI or Approved Equal Complete with rigid aluminum channel with frosted polycarbonate diffuser. Corner connectors as required. Length per RCP/Elevation (field outside). Supplier: WAC lighting
	TYPE F (Amenity, Bar) Pendant fixture Vibra Rhythm 2113-14 by Ark Levy 40x 8W LED Strip, 116W total Fix: 14 (Black) Supplier: Lightform
	TYPE G (Throughout, Millwork) Recessed cabinet light Feenix Slimstrip LED w/ flat milky lens Model # SL150 or Approved Equal 15W, 3000K c/w SL-Bracket, connectors and power supply as required. Refer to RCP and elevations for usage. Supplier: Lightform
	TYPE H (Dining Room Wall Niches) Pendant Light Delightful Bruck pendant light. Finish to match type H Refer to RCP and elevations for qty and location. Supplier: Studio 1112
	TYPE J (Dining Room) Pendant light Delightful Coburn Suspension Light, Black Matte exterior. Cold powder interior. 2x G9 Halogen Bulbs per tube (Confirm compatible LED replacement). Cord length TBD on site. 1000mm L x 80mm Dia Qty per RCP/Elevation. Supplier: Studio1112
	TYPE K (Fitness Area, Millwork) Recessed Adjustable Downlight Eurasole TE111LED 01 Black/Black Trim 16W LED Refer to RCP for location. Supplier: Litemode
	TYPE L (Spa) Recessed Shower Light Control lighting A24555 Size: 4" dia Lamp: 1 x20w compact fluorescent Finish: shower trim with frosted lens, brushed nickel Refer to RCP for qty and location. Supplier: Studio1112
	TYPE M (Barrier Free Washroom - grd and 9th floor) Surface Mounted Light Eurasole Lap 3151 Size: 18" Lamp: 5W LED, 3000K. Chrome structure, matte white diffuser Refer to RCP for qty and location. Supplier: Studio1112
	TYPE N N/A
	TYPE P (Showers) Element 3 Inch Adjustable downlight E3R- 3 in Round, Flanged Bevel Shower trim. Finish: White Supplier:
	TYPE Q (Theatre) Wall Sconce Stockholm Vertical Sconce 4" x 9" length Warrunblackened Steel 3000K Wall LED light Refer to RCP and Elevations for location. Supplier: Studio1112
	TYPE R (Suite Entry) Wall Sconce Eurasole Apt 2 Light Wall Sconce Matte Black finish for body with clear acrylic for shade 2x1W LED light Refer to RCP and Elevations for location. Supplier:
	TYPE S (Typical Corridors) Eurasole INDERECT LED TL1 Flushmount Model No. 26889 LED 25W
	TYPE T (Party Room - TV unit) Low Profile Recessed Display Light MP Lighting, L64-2.5W-3000K Narrow Flood Black Anodized Aluminum.
	TYPE U (Parking Levels) Eurasole TE11LED-22 Finish: Black / Shade: White 9W LED, 3000K. Refer to RCP for locations.
	TYPE V (Lobby, Between Wood Fins) Surface Mounted Light Eurasole Beam-Sw, 10W LED EXTRUSION, Black EP-ARC023-LED BLK 89W LED, 3000K 138" W x 10" Length as per RCP - to align with wood fins. Refer to RCP for locations. Supplier: Litemode
	TYPE W (Elevator Lobby) Eurasole Inground 3X1W LED Floor Mounted Accent Lighting 23816-015 Stainless Steel trim, flush mounted 3x 3w LED, 3000K Refer to RCP for locations. Supplier: Eurotec
	TYPE X (Lobby-over concierge desk) Pendant Light Eurasole Black carbon fiber for hanging lights and ceiling plate 7x 3w LED, 3000K Refer to RCP for locations. Supplier: Litemode
	TYPE Y (Property Management Office and Concierge Task Lamps) Table Lamp- Task Modern Forms, Bowie TL-1210 Black finish 12W LED, 3000K, dimmable Refer to Furniture plan for locations. Supplier: Studio 1112
	TYPE Z (01 Level Vestibule) Surface mounted fixture, Eurotask, Aeon Large square LED, satin nickel finish, 10.0W LED, 3000K Refer to Furniture plan for locations. Supplier: Studio 1112
	TYPE Z1 (8th Floor Corridor) Lincine SLIMS SLIMLED 6" Square LED Slim Profile Recessed Retrofit, 12W, Airight Brushed nickel finish, 12W LED, 3000K Refer to Furniture plan for locations. Supplier: Studio 1112
	TYPE Z2 (01 Level Vestibule) Surface mounted fixture, Eurotask, Aeon Large square LED, satin nickel finish, 10.0W LED, 3000K Refer to Furniture plan for locations. Supplier: Studio 1112
	TYPE Z1 (8th Floor Corridor) Lincine SLIMS SLIMLED 6" Square LED Slim Profile Recessed Retrofit, 12W, Airight Brushed nickel finish, 12W LED, 3000K Refer to Furniture plan for locations. Supplier: Studio 1112

Duplex receptacle outlet (for specialty usage in addition to Electrical Drawings)
 Floor mounted duplex receptacle outlet (for specialty usage in addition to Electrical Drawings)
 Communication for voice (phone) outlet (for specialty usage in addition to Electrical Drawings)
 Communication for data (internet) outlet (for specialty usage in addition to Electrical Drawings)
 Powerline as noted (for specialty usage in addition to Electrical Drawings)
 Cable / satellite TV outlet

DO NOT SCALE DRAWINGS.

CONTRACTOR MUST VERIFY ALL DRAWINGS, DIMENSIONS, DETAILS AND SPECIFICATIONS, AND REPORT ANY DISCREPANCIES TO ARCHITECT 31 HOURS BEFORE PROCEEDING WITH WORK. MATERIALS MAY NOT BE SUBSTITUTED WITHOUT WRITTEN APPROVAL FROM UNION 31 INC.

ALL DRAWINGS AND SPECIFICATIONS ARE INSTRUMENTS OF SERVICE AND THE PROPERTY OF UNION 31 INC. WHICH MUST BE RETURNED AT THE COMPLETION OF THE WORK.

PRINTED: 18-Sep-17

ISSUED FOR AS-BUILT

NO.	DATE	COMMENTS	INI
01	31 MAY / 17	ISSUED FOR AS-BUILT	SV

REVISIONS:

UNION31 INC.
 183 BATHURST STREET, STE. 201
 TORONTO, ON, M5T 2R7, CANADA
 TEL: 416-597-1576 FAX: 416-597-2139

PROJECT NAME:
ALEXANDRA PARK MAIN BUILDING
 BLOCK 11
 ON, Canada

PROJECT NO.: 13-949

DRAWINGS:
DOOR SCHEDULE LIGHTING & ELECTRICAL LEGEND

DATE STARTED: 07 AUG / 13	DRAWING NO.:
SCALE: NTS	ID
DRAWN BY: AP	0,0,2
APPROVED BY: KC	